
NSTALLATION INSTRUCTIONS FOR WS (WALL MOUNT, SURFACE CONDUIT) OPTION 100 SERIES PERFORMANCE SCONCES


IMPORTANT: READ ALL INSTRUCTIONS BEFORE PERFORMING ANY WORK.

BE SURE ALL POWER IS OFF PRIOR TO INSTALLING LUMINAIRE.

WARNING: LUMINAIRE MUST BE GROUNDED IN ACCORDANCE WITH APPROPRIATE CODES. FAILURE TO DO SO MAY RESULT IN SERIOUS INJURY.



- SPLICE BOX ARE TO BE USED IN THIS INSTALLATION.
 INSTALL AND SEAL ELECTRICAL FITTING(S) IN HUB(S).
 INSTALL AND SEAL PLUG(S) IN UNUSED HUB(S).
 APPLY SEALANT TO THE TWO UNUSED HOLES IN
 THE TOP ANGLED WALL OF THE SPLICE BOX.
 INSTALL CONDUIT SECTION(S) INTO FITTINGS AS
 REQUIRED.
- 2. DETERMINE MOUNTING LOCATION OF SPLICE BOX. APPLY A BEAD OF SEALANT AROUND EACH MOUNTING HOLE ON THE OUTSIDE OF THE BOX. FOR INSTALLATIONS WHERE CONDUIT ENTERS THROUGH THE BACK OF THE SPLICE BOX, APPLY A BEAD OF SEALANT ON THE OUTSIDE OF THE BOX AROUND THE CONDUIT HOLE USED. SECURE BOX TO WALL WITH 5/16" BOLTS (BY OTHERS) MAKING SURE BOX IS LEVEL.
- 3. COMPLETE CONDUIT INSTALLATION AND ROUTE SUPPLY WIRES INTO SPLICE BOX.



MOUNTING BOLT PATTERN




443561004480/A815677 REV. A Page 1 of 2



NSTALLATION INSTRUCTIONS FOR WS (WALL MOUNT, SURFACE CONDUIT) OPTION 100 SERIES PERFORMANCE SCONCES

- 4. DISCARD MOUNTING BRACKET SUPPLIED WITH FIXTURE.
- 5. MAKE ELECTRICAL CONNECTIONS. FIXTURE LINE TO SUPPLY LINE, COMMON TO COMMON AND GROUND TO GROUND INCLUDING SPLICE BOX GROUND.
- 6. PLACE SPLICES AND EXCESS WIRE IN SPLICE BOX. CAREFULLY ENGAGE HANGER BRACKET TO SPLICE BOX BEING CAREFULL NOT TO PINCH WIRES. ALLOW FIXTURE TO REST AGAINST BOX. TIGHTEN LOCKING SCREWS.
- 7. UNSCREW LENS FRAME SCREWS. SLOWLY OPEN FRAME UNTILL IT HANGS FREE. INSTALL LAMP. CLOSE AND SECURE FRAME BEING CAREFULL NOT TO OVERTIGHTEN THE SCREWS.

NOTE: LENS FRAME ASSEMBLY IS REMOVABLE BY OPENING PARTIALLY, COMPRESSING RETAINING CLIPS WITH HINGE END OF FRAME AND PULLING FORWARD.



FIXTURE INSTALLED ON WS OPTION



Philips Lighting North America